

## শেল্টার কো-অপারেটিভ হাউসিং সোসাইটি লিমিটেড

## SHELTER CO-OPERATIVE HOUSING SOCIETY LTD.

(REGD. NO. 15/CMAH OF 2001 DATED 23.05.2001)
77CC/2, ANUPAMA HOUSING COMPLEX, PHASE-II, VIP ROAD, KOLKATA - 700 052

PHONE: 2500 6787

WEBSITE: www.shelteranupama.org • EMAIL ID: shelter.anu2@gmail.com

## **NOTICE INVITING QUOTATION**

No. SCHSL/ 27/ 95 / 2019-20

Dated 08 / 02 / 2020

Subject: Notice Inviting Quotation for "Repairing works (Civil) like Sunshades, Seepage Plastering of damaged Walls / Garage area, foundation pillars etc." at the premises of Shelter Co-operative Housing Society Ltd.

Sealed quotations are invited by the Secretary, Shelter Co-operative Housing Society Ltd. for "Repairing works (Civil) like Sunshades, Seepage, Plastering of damaged Walls/Garage area, foundation pillars etc." of (total 19 blocks) from reputed Civil Contract Providers.

Scope of Works:

SI.	Name of The Work	Estimated Numbers
No.	· ·	and Areas in sq. mtr.
01.	Repairing of Sunshades	About 130 NOs.
02.	Repairing of Seepages on the outside wall of the blocks	See notes below
03.	Repairing and Re-plastering of damaged walls	See notes below
04.	Repairing and Re-plastering of damaged garage area	See notes below
05.	Repairing and Re-plastering of damaged Foundation Pillars	About 8 Nos.
06	Repairing of overhead tank Floor	See notes below

- Note:— 1) The interested Civil Contract providers are invited to inspect the site regarding various works quantity as mentioned in the scope of works along with our representative to point out and finalize the areas to be repaired, before submitting their offer.

  Job Specification:
- 1. The standard quality of cement, sand and stone chips of required size etc (only branded cement like Ambuja, ACC and good quality of sand) to be used.
- 2. All plastering (Avg. 15 mm) thick with standard building materials to be carried out.
- 3. All repairing work areas to be painted after proper treatment with using materials like Asian Paint / Berger , where ever it is necessary .
- 4 . All waste materials and garbage's should be cleared by the party after completion of work in each site .
- 5. The materials used to be checked by the Representative of SCHSL at the time of the work. Warranty of the job: Minimum 5 years.

Page 1 of 5



