

Annexure-I					
			Date:	29-Aug-25	
Roof Treatment for Water Tank Basement of 17 Nos. of Blocks except Block No. 64CC and 65CC					
Note: Providing waterproofing of walls, Vertical faces, Roof Slabs with a guarantee of waterproofing of Ten (10) Years all as per Manufacturers Specifications and Directions of Engineer all Materials, Labour, Tools & Tackles complete in all respect.					
	Description of Item	Unit of Measurement	Quoted Rate (Rs.)	Estimated Quantity	Amount in (Rs.)
1	Supplying and Applying two coats of Cementitious Compound Sika Intertol Poxiter/ nitoCoat er 140 of FOSROC/ TapeCrete P151 of CICO or approved equivalent according to manufacturers specification over Concrete Surface by rendering with 1:3 Cement Sand Mortar before application of the approved Cementitious Compound.	sft		4250	
2	Supplying and Constructing 75mm thick burnt Clay Brickwork in partition walls, Parapets etc. at all heights using Bricks of compressive Strength not less than 50 kgf/sq cm as defined in IS1077 with (1:4) Cement Sand Mortar including fair cutting, waste, bonding, plumbing, lining, levelling, raking joint, scaffolding required if any and curing as per direction of Engineer, all metaterials, tools & tackles, and labour complete in all respect.	sft		340	
	Gross Amount			Rs.	

Note: 1) Time for Completion of Work is 14 calender days since issue of Work Order.

2) 10 Years of Gu r ntnee to be provided ~~against~~ Le kges/ Seepges from the Date of Issue of Virtual Completion Certificate.

3) Quantity is indicative and Payment will be done as measured at Site after completion of Work.

Blank
DOCUMENTS ARE UPLOADED IN SHELTER WEBSITE